ENGINEERING DEPARTMENT

KOLAR DIVISION.

Abstract Notification dated 21st—22nd December 1936.

The attention of the public is invited to the notification on pages 2092-2093, Part VI of the issue of the *Mysore Gazette*, dated 24th December 1936, calling for tenders for the work of restoring Hulimangala Hosakote Hosakere, Register No. 479 of Malur Taluk.

The last date fixed for the receipt of the tenders in this Office is 2 P.M. on 25th January 1937.

Abstract Notification dated 21st—22nd December 1936.

The attention of the public is invited to the notification on pages 2093-2095, Part VI of the issue of the *Mysore Gazette*, dated 24th December 1936, calling for tenders for the work of closing the breach of Maddepalli Ramapanditharkere, Register No. 916 of Bagepalli Taluk.

The last date fixed for the receipt of the tenders in this Office is 2 P.M. on 25th January 1937.

Notification dated 2nd January 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 30th January 1937, for restoring Hulkur Badankere Register No. 523 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for restoring Hulkur Badankere Register No. 523 of Malur Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 700 has to be shown every month.

Abstract estimate for Restoring Hulkur Badankere Register No. 523 of Malur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
	Bund at R. L. 57·50 top width 4½' slope 1½ to 1 and 2·1.				
1	Rooting out trees, junglewood growth and remaining top soil and Rank Vegetation, etc.	Grades	2 0 0	7	
2	Remaining Ant-hills and filling with sand and gravel	Each	0 8 0	610	
3	Cutting grips and trenches to bund for the seat of new earth	Gr.	2 0 0	7	
4	Earthwork to bund with watering and consolidating, etc., complete	C.yds.	0 3 6	3,650	
5	Turfing the slopes of bund..	S.yds.	0 0 9	2,084	
6	Removing and resetting old stone work with new jelly backing and wedging	C.yds.	0 8 0	97	
7	New stone work	„	1 8 0	616	
8	Providing and fixing new grade stones including chistling figures painting, etc., complete ..	Each	1 8 0	8	
9	Do Index stones do.. ..	„	1 8 0	8	
10	Do Gauge stones do ..	„	15 0 0	1	
11	Do B. M. stones do.. ..	„	3 0 0	2	
12	Do Register No. and date stones ..	„	3 0 0	1	
	Total for bund, Rs. ..				
	II. Constructing a Masonry Waste Weir at R. L. 52·50 length 105' at left flank.				
1	Earthwork excavating foundation and filling in	C.yds.	0 3 0	64	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	504	
3	Burnt size stone in surki mortar	C.ft.	0 4 6	1,569	
4	Burnt stone slabs 6" thick, dressed and laid ..	S.ft.	0 5 0	448	
5	Providing jaggle joints	Each	0 12 0	13	
6	Rough stone work for apron	C.yd.	1 8 0	140	
7	Painting with cement mortar	Sqr.	3 12 0		
	Total for Waste Weir, Rs. ..				
	III. Constructing a new cast iron pipe sluice 6th diameter at R. L. 46·00.				
1	Dismantling the old sluice and filling in ..	L. S.			
2	Earthwork cut opening the bund and refilling with watering and consolidating	C.yds.	0 5 6	56	
3	Excavating foundation and filling in ..	C.yds.	0 3 0	10	
4	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	222	
5	Burnt size stone in surki mortar	C.ft.	0 4 6	236	
6	Burnt stone slabs 4" to 6" thick, dressed and laid	S.ft.	0 5 0	96	
7	Pointing with cement mortar	Sqr.	3 12 0	3·32	
8	Providing and fixing cast iron pipes of 6" diameter, carting and jointing, etc., complete	R.ft.	2 8 0	36	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
9	Providing and fixing teakwood plug and rod with locking arrangements	Each	..	1	
10	Drilling holes in orifice slabs	L. S.			
	Total for sluice, Rs. ..				

Notification dated 2nd January 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 30th January 1937, for restoring Dadinayakandoddi Jambukere Register No. 294 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Dadinayakandoddi Jambukere Register No. 294 of Malur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 700 has to be shown every month.

Abstract estimate for restoring Dadinayakandoddi, Jambukere Register No. 294 of Malur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Bund.				
1	Clearing jungle with removal of trees, roots, etc., complete..	Gr.	2 0 0	18	
2	Removing ant-hills and filling them with sand	No.	1 0 0	12	
3	Cutting grips and trenches and removing weeds, etc.	Gr.	1 0 0	18	
4	Earthwork to bund with watering and consolidation, etc.	C.yds.	0 3 6	8,272	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
5	Earthwork to bund from the earth got from waste weir only watering and consolidation, etc., complete, including lead and lift ..	C.yds.	0 1 6	817	
6	Turfing both front and rear slopes	S.yds.	0 0 9	6,485	
7	Providing and fixing grade stones into cutting figures and painting, etc.	Each.	1 8 0	18	
8	Providing and fixing Index stones including cutting and painting, etc., complete ..	Each.	0 6 0	18	
9	Do Gauge stones	„	15 0 0	1	
10	Do Registered No. and Date stone..	Each.	3 0 0	1	
11	Do B. M. stone	„	2 8 0	2	
	Total for bund, Rs. ..				
	II. Cast iron pipe sluice 7" Dia at R. L. 44·50.				
1	Earthwork cut opening the bund and refilling the same with watering and consolidating	C.yds.	0 5 0	74	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	110	
3	Burnt brick in surki mortar	C.ft.	0 4 6	271	
4	Burnt stone slabs 6" thick, dressed ..	S.ft.	0 5 0	55	
5	Plastering with surki mortar	Sqr.	4 0 0	3·02	
6	Providing plug and rod with locking arrangements, etc.	L. S.			
7	Providing 7" diameter cast iron pipes for sluice, including fixing, jointing with lead, etc., complete	R.ft.	3 0 0	27	
8	Cutting holes for orifice glass	L. S.			
9	Rough stone work	„			
10	Dismantling old masonry	„			
	Total for sluice, Rs. ..				
	III. Constructing a Waste Weir 90 ft. long at R. L. 50·00 Left Flank.				
1	Earthwork Excavating Foundations Draft and approaches and using the earth for bund	C.yds.	0 3 0	889	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	278	
3	Burnt brick in surki mortar	C.ft.	0 4 6	368	
4	Burnt stone slabs 6" thick, dressed ..	S.ft.	0 5 0	421	
5	Plastering with surki mortar	Sqr.	4 0 0	6·21	
6	Rough stone work for apron	C.yds.	1 8 0	87	
7	Jaggle joints 8 feet C. to C.	Each	1 0 0	10	
	Total for Left weir, Rs. ..				
	IV. Waste Weir 90 feet long at R. L. 50·00 Right Flank.				
1	Earthwork excavating foundation and using the earth for bund	C.yds.	0 3 0	132	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	278	
3	Burnt brick in surki mortar	C.ft.	0 4 6	616	
4	Burnt stone slabs 6" thick, dressed	S.ft.	0 5 0	441	
5	Plastering with surki mortor	Sqr.	4 0 0	8·48	
6	Rough stone work for apron	C.yds.	1 8 0	103	
7	Jaggle joints 8' C. to C.	Each	1 0 0	10	
	Total for Right Weir Rs. ..				

P. RAJAGOPALAN,
Executive Engineer.